


MURFORM

CASE STUDY

M8 WOODSIDE TEMPORARY PROPPING



Full Package Works

- Engineering support and Testing
- Groundworks
- Plant and Material Supply
- Road Protection Solutions
- Concrete Repairs
- Excavations



PILE CAPS AND CONCRETE REPAIRS



- Specialist hydro demolition and shotcrete repairs delivered utilising our partners CRL and Corecut.



- Installation of anodes as part of a cathodic protection system to mitigate reinforcement corrosion.

The repair strategy combining hydro-demolition, shotcrete applications and corrosion protection systems provided a durable, long-term solution.



- Construction of reinforced concrete pile cap bases (up to 4.4m deep).



- Installation of reinforced concrete column jackets.
- Construction of over-slab jackets on existing pile caps



BESPOKE STEEL FORMWORK AND CONCRETE PIER HEADS



Designed and manufactured for the complex structures





ENGINEERING SUPPORT AND TESTING

- Complete surveying of Fibre Reinforced Concrete (FRC) elements and as-built drawings.
- Ferro scanning to survey existing rebar.
- Structural surveys and condition assessment reports.
- Destructive and non-destructive testing on components of the existing structure.
- Resin anchored pull testing.
- Crane pad load-bearing testing.





ROAD PROTECTION SOLUTIONS





GROUNDWORKS

- Lightweight solutions for backfilling.
- Sheet piling and slope stabilisation.





PLANT


- Excavator
- Dumpers
- Rollers
- 360 Degree Roto
- Telehandlers
- Pile Croppers
- Sheet Piling
- Trench Boxes
- Hydraulic testers
- Hi-Ab Truck Mounted Cranes





Full Scope. Full Support. Job Done

Discover what we can do



CONTACT US



01506536363



www.Murform.com



@Murform Ltd